

Title: Taunton Park & Ride - Earthworks, drainage & ducting**Project Details****Client:** Somerset County Council**Consultant:** Atkins**Contract:** NEC3 Option B**Contract Value:** £850,000**Contract Period:** 1 Year**Project Overview**

M J Church undertook the bulk cut and fill earthworks to form the new Park & Ride facility to the East of Taunton.

Working for Bardon Contracting we undertook all earthworks operations (75,000m³), disposal of inert material on and off site, construction of landscape features and attenuation ponds, over 1,200m of topsoiling, installation of headwalls and construction of the car park to underside of the surfacing.

A special filter stone was used as sub-base to the car park to enable a sustainable drainage system be incorporated into the scheme. A total of 8,500m³ of stone was imported and used in the scheme.

A number of changes were incorporated into the scheme as the design was amended throughout the project, which were accommodated by M J Church and completed within the revised Contract Programme.

